

# SEMIX S100D DRY CONCRETE BATCHING PLANTS

## DRY CONCRETE BATCHING PLANTS

SMX-A-2403182140-8

### PROPOSAL

GLOBAL CONSTRUCTION SERVICES

Darren Simmons

dsimmons@globalcs.biz

+1 3176673350

United States of America (the)

#### Terms Of Payment

%50 Advance, %50 Before Shipment



**S100D PORTABLE DRY CONCRETE BATCHING PLANTS**

DESCRIPTION	AMOUNT	UNIT PRICE	TOTAL PRICE
1) S100D PORTABLE DRY CONCRETE BATCHING PLANT	1	\$280,000.00	\$280,000.00
1.1) S100D MOBILE CONCRETE BATCHING PLANT'S TOTAL CAPACITY: 100-120 YD <sup>3</sup> /H	1	-	-
1.2) AGGREGATE BIN CAPACITY: 3 X 17 TONS INLINE STORAGE BINS	1	-	-
1.3) AGGREGATE TRANSFER SYSTEM: CONVEYOR BELT	1	-	-
1.4) AGGREGATE CONVEYOR BELT POWER: 20 HP	1	-	-
1.5) AGGREGATE BATCHING: WEIGHING CONVEYOR BELT	1	-	-
1.6) AGGREGATE BATCHING CONVEYOR BELT POWER: 2 x 10 HP	1	-	-
1.7) CEMENT BATCHER: 4000 LBS	1	-	-
1.8) WATER BATCHING: BY FLOWMETER	1	-	-
1.9) CEMENT SCREW CONVEYORS: 10 inch dual augers	2	-	-
1.10) CEMENT SCREW CONVEYOR MOTOR POWER: 2 x 15 HP	1	-	-
1.11) 100 TONS CEMENT SILO WITH ALL EQUIPMENTS FROM WAM (FILTER,AUGER, FLAPS,VALVES, LEVEL INDICATORS)	1	-	-
1.12) AIR COMPRESSOR	1	-	-
1.13) 200 kVA Generator	1	-	-
		Subtotal:	\$280,000.00
		Total:	\$280,000.00
<b>TRANSPORTATION</b>			
		S100D Dry Concrete Batching Plants - (EXW Southern Port)	\$0.00
		General Total:	\$280,000.00

# Aggregate Storage Bins



Aggregate Bins Capacity & Quantity: 3 x 17 Tons (Linear) LOW PROFILE DESIGN

Bunker Discharging Gate(s): 2 Gates in each bin - Totally 6

Discharging Gates Vibrator Brand & Capacity: 700/3 - 2 Units **WAM-OLI (Italy)**

Pneumatic Piston Brand & Capacity: 6 Units Pneumatic Pistons - **Festo (Germany)**

Pneumatic Valve : 6 Units - **Festo (Germany)**

## Aggregate Batcher (Weighing Conveyor)

Batcher Capacity: 3.3 yd<sup>3</sup>

Load-cells: 4 Units

Motor Power/Gearbox: 20 HP

Vibrator: 700/3 - 2 Units - **WAM-OLI (Italy)**

Drums: 10 mm Rubber Coated

Bearings: Lubrication Grease Nipple over SNH series Scraper: V type with its weights -1 Unit

Emergency Stop Button : 1 Unit ,

Pull Rope Switch: 1 Unit





## Cement, Water, Admixture Batcher

Aggregate Batching Capacity: Designed for **3.3 yd<sup>3</sup> per batch**

## Transfer Conveyor

Belt Quality : EP 125 / 4 coats

Motor Power/Gearbox : 2 x 10 HP

Drums : 10 mm Rubber Coated

Bearings : Lubrication Grease Nipple over SNH series

Scraper : V type

Emergency Stop Button : 1 Unit

Pull-rope Switch : 1 Unit

